Example Air Pty Ltd

1 Example Street, Perth WA 6000
0400 000 000 | hello@example.com
ABN 00 000 000 000 | Licence EX00000

QUOTE

Q-2026-0002
Date 13 Nov 2026
Valid until 13 Dec 2026

PREPARED FOR

Smith

SITE ADDRESS

To be confirmed

Daikin split system installation (2.5kW)

SCOPE OF WORKS

Supply and install Daikin split system (2.5kW), reverse cycle, installed back-to-back. Includes refrigeration pipework, electrical connection with isolator, condensate drainage, commissioning and removal of rubbish.

SYSTEM SUMMARY

1	2.5 kW	Daikin	Reverse cycle
indoor unit	combined capacity	brand	operation

PRICE BREAKDOWN

Item	Qty	Unit	Unit price	Amount
Daikin 2.5kW wall split system (package)	1	ea	$1,170.00	$1,170.00
Pair coil 1/4 + 3/8 insulated copper	4	m	$15.60	$62.40
1.5mm2 4-core interconnect cable	3	m	$4.55	$13.65
80mm line-set trunking, 2m length	1	ea	$36.40	$36.40
20mm PVC condensate drain	3	m	$5.20	$15.60
20A weatherproof isolator switch	1	ea	$32.50	$32.50
20A circuit breaker	1	ea	$23.40	$23.40
2.5mm2 twin and earth power cable	10	m	$3.90	$39.00
Polymer outdoor unit slab	1	ea	$58.50	$58.50
Fixings, sealant and sundries	1	ea	$45.50	$45.50
Installation labour	4	hr	$110.00	$440.00

Subtotal (ex GST)	$1,936.95
GST (10%)	$193.70
Total (inc GST)	**$2,130.65**

TERMS

50% deposit on acceptance, balance on completion. Prices include GST where shown.
This quote is valid for 30 days from the date shown.